SANITARY AND TOWN PLANNING DIVISION.

Dated 31st December 1926.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Sanitary and Town Planning Division, up to 2 P.M. on 29th January 1927 for "Laying the Delivery Main of Tumkur Water Supply." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1927.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. Any tenders furnishing rates for units other than those specified in the statement will not be considered.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 1000 in cash or Government Promissory notes as earnest money and be superscribed "Tender for laying the Delivery Main of Tumkur Water Supply," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of setting out works, scaffolding materials, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately; but should be borne entirely, by the contractor.

10. Rates for lumpsum items in the sanctioned estimate and for items for which there is no provision in the estimate, shall be those that will be fixed by the Executive Engineer, either as per schedule of rates prevailing in market or as per data worked out with not more than 10 per cent for contractor's profit.

11. In all matters not specially provided for and in all matters of disputes about rates, quantities, measurements and quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer of Mysore will be final and legally binding.

STATEMENT.

No.	Item of work	Unit	Quantity
1	Earthwork excavation in gravelly and mooram soil and refilling the trench with watering and tamping and remaking cut up portions of road.	C.yd.	18,694
2	Earthwork excavation in soft rock and refilling the trench with watering and tamping.	do	935
3	Removing boulders	do	187
4	Blasting rock	do	187
5	Laying and jointing Cast Iron pipes 9′ to 12′ in length and fixing specials including cuts, carting the pipes from the stores (over a maximum distance of five miles) and testing the pipe line when complete.—		
	(*a*) 9″ lead joints	Joint	400
	(*b*) 9″ cement joints	do	2,700
	(*c*) 6″ lead joints	do	12
	(*d*) 6″ cement joints	do	15
6	Fixing Cast Iron Sluice and air valves with bolts, nuts and rubber insertion after overhauling the valves (all the materials being supplied by the contractor).—		
	(*a*) 9″ sluice valve	No.	1
	(*b*) 6″ sluice valve	do	3
	(*c*) Air valve	do	2
7	Rough stone revetment (at crossing, hallas) with jelly packing.	C.yd.	130
8	Rough stone apron for bed of halla and cross drains.	C.yd.	30
9	Size stone in surki mortar for pillars	C.ft.	160
10	Cement pointing to pillars	Sqr.	2·5
11	Burnt stone slabs 3″ to 4½″ thick one line dressed, laid across pillars for walking over.	S.ft.	100
12	Supplying and fixing mile stones with numbers cut and painted.	No.	6
13	Supplying and fixing furlong stones with numbers cut and painted.	do	36
14	Removing and refixing in mortar covering slabs of culverts after laying pipe line.	Sq.ft.	50
15	Earthwork excavation in hard gravelly and mooram soil.	C.yd.	54
16	Burnt stone concrete in surki mortar 1 : 2 ...	C.ft.	174
17	Burnt brick in surki mortar	Do	366
18	Burnt stone slabs 3″ to 4½″ thick two lines dressed and fixed in mortar.	Sq.ft.	144
19	Do one end rounded	do	36
20	Cement plaster 1 : 3½″ thick with corners rounded ...	Sqr.	1·5
21	Surki plaster ½″ thick with corners rounded ...	do	9
22	Drilling holes in slabs	No.	24
23	Conveying the valve cistern covers from stores and fixing with bolts and nuts and cement mortar.	do	6
24	Painting the shutters with two coats of Sidorsten paint.	Sqr.	1·98
25	Whitewash two coats	do	3·6
26	Turfing	do	2

H. F. MARKER,
Executive Engineer.

BANGALORE DIVISION.

Dated 3rd January 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P. M. on 19th January 1927 for alterations to the Reserve Police Lines at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of may 1927.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3 a. Terms should be definite quotations so much per cent or rupees less than the lowest tender will be rejected.

4. Each tender must be accompanied by a deposit of Rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for alterations to the Reserve Police Lines, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Alterations to the Reserve Police Lines at Bangalore.

No.	Items of work	Quantity	Unit	Rate
1	White washing	414·38	Sqr.	
2	Chocolate pointing	62·99	„	
3	Cement do	5·73		
4	Chunam plastering	205·33		
5	Dismantling walls	15025	C. ft.	
6	Teak wood windows with panelled and glazed shutters, iron bars, etc., iron fitting, etc., complete.	1196·25	S. ft.	
7	New Battened doors	322·00		
8	Removing doors or opening out in the walls and fixing windows including plastering brick works, etc., complete.	104	Each	
9	Burnt brick in clay	13,549	C. ft.	
10	Flooring with Cuddapah slabs on 3" concrete after removing old damaged flooring.	65·37	Sqr.	
11	Flooring with square tiles on concrete and cement pointing.	1·98	„	
12	Renewing teak wood panelled shutters	22·75	S. ft.	
13	Fixing old stone slabs	45		
14	Removing old stone slabbed compound wall ...	40·72	Sqr.	
15	Purlains of metre gauge rails	117	R. ft.	
16	Removing and re-roofing Mangalore tiled roof with rafters, reepers, etc.	196·36	Sqr.	
17	Teak wood work	48·74	C. ft.	
18	Teak wood trusses	19	Each	
19	Removing and refixing cane board	232	R. ft.	
20	Renewing teak reepers in place of damaged one ...	1,200	1,000	
21	New mortar bands	540	R. ft.	
22	Earth work	14	C. yd.	
23	Color washing	198·07	Sqr.	
24	Scraping smoothy portion of wall	141·95	„	

R. W. SCALDWELL,
Executive Engineer.